AB ENERGY SOLUTIONS
SOLAR | ELECTRICAL | O&M

**GST: 33FSQPA3244H1ZU**
Solar EPC • Electrical Infrastructure • O&M
**TNEB C-Licence Certified Enterprise**

# Quotation for 6.6 kW Grid-Connected Rooftop Solar Power System

Turnkey Engineering, Procurement, Installation & Commissioning Proposal

**Quotation No.: QT-2026-00021-V1** Package Tier: Premium Bifacial **Date: 24/10/2026**



## CUSTOMER DETAILS

Client Name: **Rajeshwar & Meenakshi Iyer**

Service Number: **045310081264 / 6.6KWp**

Quoted Capacity: **6.6 kW On-Grid Solar**

Proposal Type: **Final_Technical**

Phone: **+91 99001-84725**

Site Address:
**Villa 42, Sobha Sunbeam, Sarjapur Road, Bengaluru**

| Plant Capacity | Estimated Annual Yield | Module Performance |
|---|---|---|
| **6.6 kW On-Grid** | **~10,005 Units** | **25-30 Years Tier-1** |

**Subject: Proposal for Supply, Installation, Testing & Commissioning of 6.6 kW Grid-Connected Rooftop Solar Power System**

Dear Sir,

Thank you for giving us the opportunity to submit our quotation for your 6.6 kW Solar Rooftop Project. We are pleased to offer our professional turnkey services as detailed below.

The quotation includes the complete supply, installation, testing, and commissioning of a Grid-Connected Solar Rooftop System.

## ABOUT AB ENERGY SOLUTION

AB Energy Solution is a trusted Solar EPC & Electrical Engineering Company specializing in Project Management Consultancy (PMC), Owner's Engineer Services, Solar EPC, Installation, Testing & Commissioning (I&C), HT/LT Electrical Works, and Solar Material Supply.

With 12+ years of industry experience, we have successfully completed 50+ Solar & Electrical Projects across Residential, Commercial, Industrial, and Agricultural sectors. Our team includes TNEB C Licence Certified Engineers and experienced professionals dedicated to delivering projects with the highest standards of Quality, Safety, and On-Time Delivery.

We provide complete end-to-end solar solutions, from Site Survey, Design, Engineering, Procurement, Installation, Testing & Commissioning to Net Metering, CEIG Documentation, and Annual Maintenance (O&M).

**Quality & Compliance Assurance**

All engineering designs, structural fabrications, module installations, and electrical grid synchronizations are performed strictly complying with MNRE standards, CEA technical regulations, DISCOM grid codes, and TANGEDCO net-metering protocols.

AB ENERGY
SOLUTIONS
SOLAR | ELECTRICAL | O&M

## OUR SERVICES

- Solar Rooftop EPC Projects
- Ground Mounted Solar Power Plants
- Project Management Consultancy (PMC)
- Owner's Engineer Services
- Installation, Testing & Commissioning (I&C)
- Solar Water Pump Systems
- HT & LT Electrical Works
- Transmission Line & Pole Yard Works
- Net Metering & CEIG Approval Support
- Operation & Maintenance (O&M)
- Solar Material Supply

## WHY CHOOSE AB ENERGY SOLUTION?

- 12+ Years of Industry Experience
- 50+ Successfully Completed Projects
- TNEB C Licence Certified Engineers
- Quality Workmanship & Safety Standards
- Professional Project Management
- On-Time Project Delivery
- Transparent Communication
- Reliable After-Sales Support

### Our Commitment

Quality • Safety • Innovation • Integrity • Customer Satisfaction

### Our Vision

*"To deliver sustainable, reliable, and high-quality solar energy solutions that create long-term value for our customers and contribute to a greener future."*

AB ENERGY
SOLUTIONS
SOLAR | ELECTRICAL | O&M

## Scope of Work

We will execute the complete following turnkey EPC activities:

- Site Survey
- Engineering Support
- Supply of Material
- Complete Installation
- Testing & Commissioning
- Service Support

## Bill Of Materials

| S.NO | MATERIALS | SPECIFICATION | MAKE | UNITS | QUANTITY |
|---|---|---|---|---|---|
| 1 | **Panels** | 12 × Jinko 575W Tiger Neo N-Type TOPCon Bifacial Module | Jinko | Nos | **12** |
| 2 | **Inverter** | 10 kW Three-Phase 415V Grid Inverter with Dual MPPT & DC Switch | Sungrow | Unit | **1** |
| 3 | **Structure** | Heavy Duty 80-micron HDG elevated mounting structure with SS304 fasteners | AB | kW | **6.6** |
| 4 | **Protection & BOS** | ACDB & DCDB with Type-II SPDs, Polycab Solar DC/AC Cables, Chemical Earthing Pits & ESE | Schneider | Set | **1** |
| 5 | **Installation & Commissioning** | Complete civil mounting, cable routing in conduits, safety labeling, DISCOM net-metering liaison and synchronization | AB | Turnkey | **1** |

**Note: As this project is proposed under the Government Subsidy Scheme, all supplied solar modules must comply with the Domestic Content Requirement (DCR) guidelines.**

AB ENERGY
SOLUTIONS
SOLAR | ELECTRICAL | O&M

## Client Scope

- '¢ Provide a shadow-free installation area.
- '¢ Minor civil works, if required.
- '¢ Statutory charges for Bi-Directional Net Meter.
- '¢ Non-statutory charges related to Net Metering.
- '¢ Additional charges for elevated structures (if applicable).
- '¢ SIM card for the Wi-Fi monitoring dongle / APFC.

## Features and Warranty

- Tier-1 High-Efficiency Solar Modules
- Inverter Warranty: Up to 8 Years
- Solar Module Product Warranty: 12 Years
- Solar Module Performance Warranty: Up to 30 Years
- Workmanship Warranty: 1 Year
- Estimated Energy Generation: ~33 kWh/day
- Non DCR / DCR Solar Panels as applicable
- Compliant with MNRE and DISCOM Standards

## System Capacity & Pricing

| System Capacity | Domestic Price (Including GST) | Govt Subsidy / Net Cost |
|---|---|---|
| **6.6KW On-grid Solar System** | **¹3,24,578/-** | **Subsidy: ¹78,000**<br>**Net Cost: ¹2,46,578/-** |

## Payment Terms

- **90% Advance Payment with Purchase Order / Agreement**
- **10% After Successful Commissioning & Grid Synchronization**

## Terms & Conditions

- Quotation Validity: 7 Days from issue date.
- GST is included in the above quoted price.
- Additional civil work will be charged extra 800/kW.
- Net Meter approval is subject to TANGEDCO / DISCOM regulations.
- Delivery is subject to material readiness and site access.
- Any additional civil or electrical work outside the quoted scope will be charged extra.
- Elevated above 4 Feet mounting structures will be charged extra 2500 per kW.
- Force majeure conditions and DISCOM grid outages are excluded.

**Thank you for your valuable opportunity. We look forward to delivering a reliable solar solution and building a long-term partnership with you.**

## Contact Details

**A Boopathi BE.,**
**CEO & Managing Director • AB ENERGY SOLUTIONS**
Phone: +91 95664 99678 | Email: abenergysolutiontn@gmail.com
1/359, Maruthi Nagar, Chinnakavandanur, Namakkal, TN - 636202
**12+ Years Solar Experience • TNEB C-Licence Certified Enterprise**

**For AB ENERGY SOLUTIONS**

Authorized Signatory

AB ENERGY
SOLUTIONS
SOLAR | ELECTRICAL | O&M