# AB ENERGY SOLUTIONS

Certified Tier-1 Solar EPC & Clean Energy Infrastructure • GSTIN: 29AABCS1429B1Z8
Indiranagar, Bengaluru, KA 560038 • support@abenergy.in • +91 80 4920 1888

## TECHNO-COMMERCIAL PROPOSAL

REF: QT-2026-00023-V1 (Ver 1)
Proposal Date: 23/10/2026

### CLIENT & PROJECT DETAILS

Client Name: Ramesh Kumar (Test)
Contact: +91 98450-99881
Site Address: Indiranagar, Bengaluru, Karnataka

### TECHNICAL SIZING SPECIFICATIONS

System Capacity: 6.5 kW DC (6.9 kWp)
Package Tier: Premium Bifacial
Valid Until: 2026-11-06 (14 Days) • Prepared By: Project Manager

## EQUIPMENT BILL OF MATERIALS (BOM) & STATUTORY GST BREAKDOWN

| # | MATERIAL / SCOPE OF WORK | HSN/SAC | QTY | RATE ( ¹) | TAXABLE ( ¹) | GST % | TAX ( ¹) | TOTAL ( ¹) |
|---|---|---|---|---|---|---|---|---|
| 1 | **12 × Jinko 575W Tiger Neo N-Type TOPCon Bifacial Module**<br>Make: Jinko 575W Tiger Neo N-Type TOPCon Bifacial Module • 12-Yr Product / 25-Yr Linear Performance | 8541 | 12 Nos | ¹12,800 | ¹1,53,600 | **5%** | ¹7,680 | **¹1,61,280** |
| 2 | **10 kW Three-Phase 415V Grid Inverter with Dual MPPT & DC Switch**<br>Make: Sungrow SG10RT 3-Phase • 10-Yr Replacement Warranty | 8504 | 1 Unit | ¹68,000 | ¹68,000 | **5%** | ¹3,400 | **¹71,400** |
| 3 | **Heavy Duty 80-micron HDG elevated mounting structure with SS304 fasteners**<br>Make: AB Solar HDG Custom Fabricated • 10-Yr Anti-Corrosion Warranty | 7308 | 6.5 kW | ¹2,800 | ¹18,200 | **18%** | ¹3,276 | **¹21,476** |
| 4 | **ACDB & DCDB with Type-II SPDs, Polycab Solar DC/AC Cables, Chemical Earthing Pits & ESE Lightning Arrester**<br>Make: Schneider / L&T / Polycab • 5-Yr Comprehensive Warranty | 8544 | 1 Set | ¹31,200 | ¹31,200 | **18%** | ¹5,616 | **¹36,816** |
| 5 | **Complete civil mounting, cable routing in conduits, safety labeling, DISCOM net-metering liaison and synchronization**<br>Make: AB Energy Solutions Certified EPC Crew • 5-Yr Comprehensive Workmanship & O&M | 9954 | 1 Turnkey | ¹27,300 | ¹27,300 | **18%** | ¹4,914 | **¹32,214** |

**Amount in Words:** Rupees Three Lakh Twenty Three Thousand One Hundred Eighty Six Only

### ESTIMATED GENERATION & SOLAR PAYBACK

Estimated Annual Yield: ~10,005 kWh / yr

Annual Grid Bill Savings: ~ ¹82,041 / yr

25-Year Cumulative Savings: ~ ¹20,51,025

Estimated Simple Payback: ~3 Years

*Calculated at 1,450 kWh/kWp specific yield & ¹8.20/kWh average grid tariff.
*Actual solar generation depends on local irradiance and tilt angle.

| | |
|---|---|
| Gross Equipment Subtotal: | ¹2,98,300 |
| **Net Taxable Base Value:** | **¹2,98,300** |
| Central GST (CGST): | ¹12,443 |
| State GST (SGST): | ¹12,443 |
| **FINAL CONTRACT VALUE:** | **¹3,23,186** |
| PM Surya Ghar Subsidy (Direct Benefit): | - ¹78,000 |
| **Indicative Net Out-of-Pocket:** | **¹2,45,186** |

## MILESTONE PAYMENT SCHEDULE & TERMS

- 40% Advance on project booking and detailed engineering approval.
- 50% upon material dispatch against warehouse delivery challan.
- 10% upon successful DISCOM net-metering synchronization and commissioning sign-off.
- Quotation valid for 14 calendar days from date of issuance.
- Central subsidy under PM Surya Ghar is credited directly by the Government to the customer bank account post DISCOM inspection via DBT.

For AB Energy Solutions (Authorized Signatory):

**Project Manager**

**Client Acceptance Signature:**

**I accept the above proposal terms & BOM scope.**