AB ENERGY SOLUTIONS

Certified Tier-1 Solar EPC & Clean Energy Infrastructure • GSTIN: 29AABCS1429B1Z8
Indiranagar, Bengaluru, KA 560038 • support@abenergy.in • +91 80 4920 1888

TECHNO-COMMERCIAL PROPOSAL

REF: QT-2026-00022-V1 (Ver 1)
Date: 24/10/2026

CLIENT & PROJECT DETAILS

Client Name: M/s Kirloskar Auto Components & Tooling Ltd.
Contact Phone: +91 98450-71289
Site Location: Plot 44-B, 2nd Phase, Peenya Industrial Area, Bengaluru

TECHNICAL SIZING SPECIFICATIONS

System Capacity: 45 kW DC (45.42 kWp)
Package Tier: Premium Bifacial
Valid Until: 2026-11-07 (14 Days) • Sales: Ananya Deshmukh

EQUIPMENT BILL OF MATERIALS (BOM) & STATUTORY GST BREAKDOWN

#	MATERIAL / SCOPE OF WORK	HSN/SAC	QTY	RATE (₹)	TAXABLE (₹)	GST %	TAX (₹)	TOTAL (₹)
1	**79 × Jinko 575W Tiger Neo N-Type TOPCon Bifacial Module** Make: Jinko 575W Tiger Neo N-Type TOPCon Bifacial Module • 12-Yr Product / 25-Yr Linear Performance	8541	79 Nos	₹12,800	₹10,05,374	**5%**	₹50,269	**₹10,55,643**
2	**45 kW Commercial Multi-MPPT High Yield Solar Inverter** Make: Growatt MAX / Sungrow Commercial • 10-Yr Replacement Warranty	8504	1 Unit	₹1,93,500	₹1,92,385	**5%**	₹9,619	**₹2,02,004**
3	**Heavy Duty 80-micron HDG elevated mounting structure with SS304 fasteners** Make: AB Solar HDG Custom Fabricated • 10-Yr Anti-Corrosion Warranty	7308	45 kW	₹2,800	₹1,25,274	**18%**	₹22,549	**₹1,47,823**
4	**ACDB & DCDB with Type-II SPDs, Polycab Solar DC/AC Cables, Chemical Earthing Pits & ESE Lightning Arrester** Make: Schneider / L&T / Polycab • 5-Yr Comprehensive Warranty	8544	1 Set	₹2,16,000	₹2,14,756	**18%**	₹38,656	**₹2,53,412**
5	**Complete civil mounting, cable routing in conduits, safety labeling, DISCOM net-metering liaison and synchronization** Make: AB Energy Solutions Certified EPC Crew • 5-Yr Comprehensive Workmanship & O&M	9954	1 Turnkey	₹1,89,000	₹1,87,911	**18%**	₹33,824	**₹2,21,735**

Amount in Words: Rupees Eighteen Lakh Eighty Thousand Six Hundred Seventeen Only

ESTIMATED GENERATION & SOLAR PAYBACK

Estimated Annual Yield: ~65,859 kWh / yr

Annual Grid Bill Savings: ~ ₹5,40,044 / yr

25-Year Cumulative Savings: ~ ₹1,35,01,100

Estimated Simple Payback: ~3.5 Years

*Calculated at 1,450 kWh/kWp specific yield & ₹8.20/kWh average grid tariff.
*Actual solar generation depends on local irradiance and rooftop tilt angle.

Gross Equipment Subtotal:	₹17,35,700
Commercial Discount:	- ₹10,000
Net Taxable Base Value:	**₹17,25,700**
Central GST (CGST):	₹77,460
State GST (SGST):	₹77,457
FINAL CONTRACT VALUE:	**₹18,80,617**

MILESTONE PAYMENT SCHEDULE & TERMS

- 40% Advance on project booking and detailed engineering approval.
- 50% upon material dispatch against warehouse delivery challan.
- 10% upon successful DISCOM net-metering synchronization and commissioning sign-off.
- Quotation valid for 14 calendar days from date of issuance.

For AB Energy Solutions (Authorized Signatory):

Ananya Deshmukh

Client Acceptance Signature:

I accept the above proposal terms & BOM scope.