AB ENERGY SOLUTIONS

Certified Tier-1 Solar EPC & Clean Energy Infrastructure • GSTIN: 29AABCS1429B1Z8
Indiranagar, Bengaluru, KA 560038 • support@abenergy.in • +91 80 4920 1888

TECHNO-COMMERCIAL PROPOSAL

REF: QT-2026-TEST-STD (Ver 1)
Date: 23/10/2026

CLIENT & PROJECT DETAILS

Client Name: Karthik Venkataraman
Contact Phone: +91 98450 12345
Site Location: 42, 12th Main, HAL 2nd Stage, Indiranagar, Bengaluru, Karnataka 560038

TECHNICAL SIZING SPECIFICATIONS

System Capacity: 5 kW DC (5.17 kWp)
Package Tier: Premium Bifacial
Valid Until: 2026-11-06 (14 Days) • Sales: Vikram Mehta

EQUIPMENT BILL OF MATERIALS (BOM) & STATUTORY GST BREAKDOWN

#	MATERIAL / SCOPE OF WORK	HSN/SAC	QTY	RATE (₹)	TAXABLE (₹)	GST %	TAX (₹)	TOTAL (₹)
1	**9 × Jinko 575W Tiger Neo N-Type TOPCon Bifacial Modules** Make: Jinko Solar Tiger Neo 575W (ALMM Tier-1) • 12-Yr Product / 30-Yr Linear Performance	8541	9 Nos	₹12,800	₹1,11,327	5%	₹5,566	**₹1,16,893**
2	**Growatt 5kW Dual-MPPT High Efficiency Cloud Inverter** Make: Growatt MIN 5000TL-X Smart Cloud Inverter • 10-Yr Replacement Warranty	8504	1 Unit	₹48,000	₹46,386	5%	₹2,320	**₹48,706**
3	**AB Solar HDG Custom Elevated Rooftop Structure** Make: Hot-Dip Galvanized 80-Micron Cold-Rolled Steel • 15-Yr Wind Load & Anti-Corrosion Guarantee	7308	5 kW	₹9,000	₹43,487	18%	₹7,828	**₹51,315**
4	**DCDB, ACDB, Type-II SPD, Polycab Solar DC Cables & Chemical Earthing** Make: Schneider / L&T / Polycab Dual-Core Cu • 5-Yr Workmanship & Comprehensive BOS	8544	1 Set	₹28,000	₹27,059	18%	₹4,870	**₹31,929**
5	**Complete Engineering, Clamping, DISCOM Net-Metering Liasoning & CEIG Testing** Make: AB Energy Solutions Certified EPC Crew • 5-Yr Comprehensive Workmanship & Free O&M	9954	1 Turnkey	₹35,000	₹33,824	18%	₹6,088	**₹39,912**

Amount in Words: Rupees Two Lakh Eighty-Eight Thousand Seven Hundred Fifty-Five Only

ESTIMATED GENERATION & SOLAR PAYBACK

Estimated Annual Yield: ~7,500 kWh / yr

Annual Grid Bill Savings: ~ ₹61,500 / yr

25-Year Cumulative Savings: ~ ₹15,37,500

Estimated Simple Payback: ~3.4 Years

*Calculated at 1,450 kWh/kWp specific yield & ₹8.20/kWh average grid tariff.
*Actual solar generation depends on local irradiance and rooftop tilt angle.

Gross Equipment Subtotal:	₹2,71,200
Commercial Discount:	- ₹9,117
Net Taxable Base Value:	**₹2,62,083**
Central GST (CGST):	₹13,336
State GST (SGST):	₹13,336
FINAL CONTRACT VALUE:	**₹2,88,755**
PM Surya Ghar Subsidy (Direct Benefit):	- ₹78,000
Indicative Net Out-of-Pocket:	**₹2,10,755**

MILESTONE PAYMENT SCHEDULE & TERMS

- 40% Advance on signing contract and engineering layout signoff.
- 40% Upon warehouse material dispatch & physical site delivery.
- 20% Upon successful system testing, commissioning & net-metering synchronization.
- Quotation validity is 14 days from date of issue.

For AB Energy Solutions (Authorized Signatory):

Vikram Mehta

Client Acceptance Signature:

I accept the above proposal terms & BOM scope.