Quotation for 20 kW Grid-Connected Rooftop Solar Power System

Quotation No.: ABES/RT/2026/0148

Date: 26/10/2026



CUSTOMER DETAILS

Client Name: Vikrant Deshpande

Phone: +91 97412-55890

Service Number: XXX / 20KWp

Site Address: 228, Sathya nagar, North Ammapet, Salem, Tamil Nadu

Quoted Capacity: 20 kW On-Grid

Subject: Proposal for Supply, Installation, Testing & Commissioning of 20 kW Grid-Connected Rooftop Solar Power System

Dear Sir,

Thank you for giving us the opportunity to submit our quotation for your 20 kW Solar Rooftop Project. We are pleased to offer our turnkey engineering and EPC services as detailed below.

The quotation includes the complete supply, installation, testing, and commissioning of a Grid-Connected Solar Rooftop System.

ABOUT AB ENERGY SOLUTION

AB Energy Solution is a professionally managed Solar EPC and Electrical Engineering enterprise, delivering reliable, high-yield, and cost-effective solar energy solutions for residential, commercial, industrial, and agricultural sectors.

The company is led by Mr. A. Boopathi, B.E., Managing Director, who brings 12+ years of hands-on experience in the Solar EPC and Electrical Engineering industry. Under his technical leadership, 50+ solar and electrical projects have been successfully executed with a strong focus on quality, safety, and timely project delivery.

Our technical team includes TNEB C Licence Certified Engineers and skilled professionals, ensuring every project is executed in accordance with industry standards, MNRE guidelines, and client requirements.

OUR SERVICES

- Solar Rooftop EPC Projects
- Ground Mounted Solar Power Plants
- Project Management Consultancy (PMC)
- Owner's Engineer Services
- Installation, Testing & Commissioning (I&C)
- Solar Water Pump Systems
- HT & LT Electrical Works
- Transmission Line & Pole Yard Works
- Net Metering & CEIG Approval Support
- Operation & Maintenance (O&M)
- Solar Material Supply

WHY CHOOSE AB ENERGY SOLUTION?

- 12+ Years of Industry Experience
- 50+ Successfully Completed Projects
- TNEB C Licence Certified Engineers
- Quality Workmanship & Safety Standards
- Professional Project Management
- On-Time Project Delivery
- Transparent Communication
- Reliable After-Sales Support

Our Commitment: Quality • Safety • Innovation • Integrity • Customer Satisfaction

"To deliver sustainable, reliable, and high-quality solar energy solutions that create long-term value for our customers and contribute to a greener future."

Scope of Work

We will execute the complete turnkey engineering and EPC activities as below:

- Site Survey
- Engineering Support
- Supply of Material
- Complete Installation
- Testing & Commissioning
- Service support

Bill Of Materials

S.NO	MATERIALS	SPECIFICATION	MAKE	UNITS	QUANTITY
1	solar panels	600-630Wp Topcon panel	Waaree/Adani/Vikram/Premier	KWp	20
2	Inverter	20KW/3 Phase	Solis/Sungrow	Nos	1
3	Structure	Pre- Galvanized/Mini Rail	Reputed	Set	1
4	DCDB	63A With SPD	Reputed	Nos	1
5	ACDB	3PN/63A MCB	Reputed	Nos	1
6	Earth Electrode	Coper Bonded 100 Micron,19mm dia,1.2Mtr	Reputed	Nos	3
7	Earthing Wire	6 Sq mm Copper wire	polycab/RR cable	Mtrs	90
8	Lightning Arrester	Coper Bonded 100 Micron,19mm dia,1.2Mtr	Reputed	Nos	1
9	PVC pipe	1 inch	Reputed	Nos	1
10	MC4 Connector	1000V DC, IP68	Staubli	Sets	3
11	DC cable	6Sqmm copper cable	Polycab / Equivalen	Mtrs	200
12	AC Cable	3.5 Core × 35 Sq.mm al.armd Cable	Polycab / Equivalen	Mtrs	35
13	SS Bolt &Nuts	M8x25 SS203 grade	Reputed	Sets	1
14	Other Accessories	As Required	Reputed	Sets	1

Note: As this project is proposed under the Government Subsidy Scheme, all supplied solar modules must comply with the Domestic Content Requirement (DCR) guidelines.

AB ENERGY SOLUTIONS
SOLAR | ELECTRICAL | O&M

Client Scope

'¢ Provide a shadow-free installation area.
'¢ Minor civil works, if required.
'¢ Statutory charges for Bi-Directional Net Meter.
'¢ Non-statutory charges related to Net Metering.
'¢ Additional charges for elevated structures (if applicable).
'¢ SIM card for Wi-Fi monitoring / Power factor APFC.

Features and Warranty

- Tier-1 High-Efficiency Solar Modules
- Inverter Warranty: Up to 8 Years
- Solar Module Product Warranty: 12 Years
- Solar Module Performance Warranty: Up to 30 Years
- Workmanship Warranty: 1 Year
- Estimated Generation: ~100 kWh/day (Subject to weather)
- The solar panels are Non DCR / DCR as applicable
- Suitable for Residential, Commercial & Industrial Installations

System Capacity & Pricing

System Capacity	Domestic Price (Including GST)	ROI
20KW On-grid Solar System	**7,98,100/-**	**3.5 years**

Payment Terms

- **90% Advance Payment with Purchase Order / Agreement**
- **10% After Successful Commissioning & Grid Synchronization**

Terms & Conditions

- Quotation Validity: 7 Days from issue date.
- Including GST above price.
- Net Meter approval is subject to TANGEDCO / DISCOM regulations.
- Delivery is subject to material readiness and site access.
- Any additional civil/electrical work outside the quoted scope will be charged extra.
- If need Zero Export Device extra.
- Force majeure conditions and DISCOM grid outages are excluded.

Contact Details

A Boopathi BE.,
CEO & Managing Director • AB ENERGY SOLUTIONS
Phone: +91 95664 99678 | Email: abenergysolutiontn@gmail.com
1/359, Maruthi Nagar, Chinnakavandanur, Namakkal, TN - 636202
10+ Years Solar Experience • TNEB Competency Certified

For AB ENERGY SOLUTIONS

Authorized Signatory