AB ENERGY SOLUTIONS

Certified Tier-1 Solar EPC & Clean Energy Infrastructure • GSTIN: 29AABCS1429B1Z8
Indiranagar, Bengaluru, KA 560038 • support@abenergy.in • +91 80 4920 1888

TECHNO-COMMERCIAL PROPOSAL

REF: QT-2026-TEST-LONG-DESC (Ver 1)
Date: 23/10/2026

CLIENT & PROJECT DETAILS

Client Name: Karthik Venkataraman
Contact Phone: +91 98450 12345
Site Location: 42, 12th Main, HAL 2nd Stage, Indiranagar, Bengaluru, Karnataka 560038

TECHNICAL SIZING SPECIFICATIONS

System Capacity: 5 kW DC (5.17 kWp)
Package Tier: Premium Bifacial
Valid Until: 2026-11-06 (14 Days) • Sales: Vikram Mehta

EQUIPMENT BILL OF MATERIALS (BOM) & STATUTORY GST BREAKDOWN

#	MATERIAL / SCOPE OF WORK	HSN/SAC	QTY	RATE (₹)	TAXABLE (₹)	GST %	TAX (₹)	TOTAL (₹)
1	**Waaree 550W High-Efficiency Half-Cut Monocrystalline Bifacial Solar PV Modules with Dual-Glass Encapsulation, Anti-PID Technology, Low Irradiance Performance and 21.3% Cell Efficiency for Extreme Weather Conditions** Make: Waaree Energies WXS-550 (ALMM Listed Tier-1 Premium) • 12-Yr Comprehensive Product Workmanship / 30-Yr Linear 84.8% Power Output Warranty	8541	18 Nos	₹11,500	₹2,07,000	**5%**	₹10,350	**₹2,17,350**
2	**Sungrow 10kW Three-Phase High Yield Commercial String Inverter with Dual Maximum Power Point Tracking (MPPT), 150% DC Overload Capacity, Integrated Smart IV Curve Scanning and Arc Fault Circuit Interrupter (AFCI)** Make: Sungrow SG10RT Grid-Tied Inverter with Built-in WiFi / Ethernet Communication • 10-Yr Full Replacement Warranty with 24-Hr Service Support	8504	1 Unit	₹72,000	₹72,000	**5%**	₹3,600	**₹75,600**
3	**Custom HDG Elevated Superstructure Elevated to 3.0 Meters for Terrace Utilization with Wind Resistance certified up to 170 km/h as per IS 875 Part 3, complete with M12 Anchor Fasteners and Chemical Grouting** Make: Tata Steel HDG Sections (Minimum 80-Micron Zinc Coating) • 25-Yr Anti-Rust & Structural Integrity Guarantee	7308	10 kW	₹9,500	₹95,000	**18%**	₹17,100	**₹1,12,100**

Amount in Words: Rupees Two Lakh Eighty-Eight Thousand Seven Hundred Fifty-Five Only

ESTIMATED GENERATION & SOLAR PAYBACK

Estimated Annual Yield: ~7,500 kWh / yr

Annual Grid Bill Savings: ~ ₹61,500 / yr

25-Year Cumulative Savings: ~ ₹15,37,500

Estimated Simple Payback: ~3.4 Years

*Calculated at 1,450 kWh/kWp specific yield & ₹8.20/kWh average grid tariff.

*Actual solar generation depends on local irradiance and rooftop tilt angle.

Gross Equipment Subtotal:	₹2,71,200
Commercial Discount:	- ₹9,117
Net Taxable Base Value:	**₹2,62,083**
Central GST (CGST):	₹13,336
State GST (SGST):	₹13,336
FINAL CONTRACT VALUE:	**₹2,88,755**
PM Surya Ghar Subsidy (Direct Benefit):	- ₹78,000
Indicative Net Out-of-Pocket:	**₹2,10,755**

MILESTONE PAYMENT SCHEDULE & TERMS

- 40% Advance on signing contract and engineering layout signoff.
- 40% Upon warehouse material dispatch & physical site delivery.
- 20% Upon successful system testing, commissioning & net-metering synchronization.
- Quotation validity is 14 days from date of issue.

For AB Energy Solutions (Authorized Signatory):

Vikram Mehta

Client Acceptance Signature:

I accept the above proposal terms & BOM scope.