AB ENERGY SOLUTIONS

Certified Tier-1 Solar EPC & Clean Energy Infrastructure • GSTIN: 29AABCS1429B1Z8
Indiranagar, Bengaluru, KA 560038 • support@abenergy.in • +91 80 4920 1888

TECHNO-COMMERCIAL PROPOSAL

REF: QT-2026-00025-V1 (Ver 1)
Proposal Date: 23/10/2026

CLIENT & PROJECT DETAILS

Client Name: Ramesh Kumar (Test)
Contact: +91 98450-99881
Site Address: Indiranagar, Bengaluru, Karnataka

TECHNICAL SIZING SPECIFICATIONS

System Capacity: 6.5 kW DC (6.9 kWp)
Package Tier: Premium Bifacial
Valid Until: 2026-11-06 (14 Days) • Prepared By: Project Manager

EQUIPMENT BILL OF MATERIALS (BOM) & STATUTORY GST BREAKDOWN

#	MATERIAL / SCOPE OF WORK	HSN/SAC	QTY	RATE (¹)	TAXABLE (¹)	GST %	TAX (¹)	TOTAL (¹)
1	**12 × Jinko 575W Tiger Neo N-Type TOPCon Bifacial Module** Make: Jinko 575W Tiger Neo N-Type TOPCon Bifacial Module • 12-Yr Product / 25-Yr Linear Performance	8541	12 Nos	¹12,800	¹1,53,600	**5%**	¹7,680	**¹1,61,280**
2	**10 kW Three-Phase 415V Grid Inverter with Dual MPPT & DC Switch** Make: Sungrow SG10RT 3-Phase • 10-Yr Replacement Warranty	8504	1 Unit	¹68,000	¹68,000	**5%**	¹3,400	**¹71,400**
3	**Heavy Duty 80-micron HDG elevated mounting structure with SS304 fasteners** Make: AB Solar HDG Custom Fabricated • 10-Yr Anti-Corrosion Warranty	7308	6.5 kW	¹2,800	¹18,200	**18%**	¹3,276	**¹21,476**
4	**ACDB & DCDB with Type-II SPDs, Polycab Solar DC/AC Cables, Chemical Earthing Pits & ESE Lightning Arrester** Make: Schneider / L&T / Polycab • 5-Yr Comprehensive Warranty	8544	1 Set	¹31,200	¹31,200	**18%**	¹5,616	**¹36,816**
5	**Complete civil mounting, cable routing in conduits, safety labeling, DISCOM net-metering liaison and synchronization** Make: AB Energy Solutions Certified EPC Crew • 5-Yr Comprehensive Workmanship & O&M	9954	1 Turnkey	¹27,300	¹27,300	**18%**	¹4,914	**¹32,214**

Amount in Words: Rupees Three Lakh Twenty Three Thousand One Hundred Eighty Six Only

ESTIMATED GENERATION & SOLAR PAYBACK

Estimated Annual Yield: ~10,005 kWh / yr

Annual Grid Bill Savings: ~ ¹82,041 / yr

25-Year Cumulative Savings: ~ ¹20,51,025

Estimated Simple Payback: ~3 Years

*Calculated at 1,450 kWh/kWp specific yield & ¹8.20/kWh average grid tariff.

*Actual solar generation depends on local irradiance and tilt angle.

Gross Equipment Subtotal:	¹2,98,300
Net Taxable Base Value:	**¹2,98,300**
Central GST (CGST):	¹12,443
State GST (SGST):	¹12,443
FINAL CONTRACT VALUE:	**¹3,23,186**
PM Surya Ghar Subsidy (Direct Benefit):	- ¹78,000
Indicative Net Out-of-Pocket:	**¹2,45,186**

MILESTONE PAYMENT SCHEDULE & TERMS

- 40% Advance on project booking and detailed engineering approval.
- 50% upon material dispatch against warehouse delivery challan.
- 10% upon successful DISCOM net-metering synchronization and commissioning sign-off.
- Quotation valid for 14 calendar days from date of issuance.
- Central subsidy under PM Surya Ghar is credited directly by the Government to the customer bank account post DISCOM inspection via DBT.

For AB Energy Solutions (Authorized Signatory):

Project Manager

Client Acceptance Signature:

I accept the above proposal terms & BOM scope.