AB ENERGY SOLUTIONS

Certified Tier-1 Solar EPC & Clean Energy Infrastructure • GSTIN: 29AABCS1429B1Z8
Indiranagar, Bengaluru, KA 560038 • support@abenergy.in • +91 80 4920 1888

TECHNO-COMMERCIAL PROPOSAL

REF: QT-2026-TEST-MULTI-12 (Ver 1)
Date: 23/10/2026

CLIENT & PROJECT DETAILS

Client Name: Karthik Venkataraman
Contact Phone: +91 98450 12345
Site Location: 42, 12th Main, HAL 2nd Stage, Indiranagar, Bengaluru, Karnataka 560038

TECHNICAL SIZING SPECIFICATIONS

System Capacity: 5 kW DC (5.17 kWp)
Package Tier: Premium Bifacial
Valid Until: 2026-11-06 (14 Days) • Sales: Vikram Mehta

EQUIPMENT BILL OF MATERIALS (BOM) & STATUTORY GST BREAKDOWN

#	MATERIAL / SCOPE OF WORK	HSN/SAC	QTY	RATE (₹)	TAXABLE (₹)	GST %	TAX (₹)	TOTAL (₹
1	**9 × Jinko 575W Tiger Neo N-Type TOPCon Bifacial Modules** Make: Jinko Solar Tiger Neo 575W (ALMM Tier-1) • 12-Yr Product / 30-Yr Linear Performance	8541	9 Nos	₹12,800	₹1,11,327	5%	₹5,566	**₹1,16,893**
2	**Growatt 5kW Dual-MPPT High Efficiency Cloud Inverter** Make: Growatt MIN 5000TL-X Smart Cloud Inverter • 10-Yr Replacement Warranty	8504	1 Unit	₹48,000	₹46,386	5%	₹2,320	**₹48,706**
3	**AB Solar HDG Custom Elevated Rooftop Structure** Make: Hot-Dip Galvanized 80-Micron Cold-Rolled Steel • 15-Yr Wind Load & Anti-Corrosion Guarantee	7308	5 kW	₹9,000	₹43,487	18%	₹7,828	**₹51,315**
4	**DCDB, ACDB, Type-II SPD, Polycab Solar DC Cables & Chemical Earthing** Make: Schneider / L&T / Polycab Dual-Core Cu • 5-Yr Workmanship & Comprehensive BOS	8544	1 Set	₹28,000	₹27,059	18%	₹4,870	**₹31,929**
5	**Complete Engineering, Clamping, DISCOM Net-Metering Liasoning & CEIG Testing** Make: AB Energy Solutions Certified EPC Crew • 5-Yr Comprehensive Workmanship & Free O&M	9954	1 Turnkey	₹35,000	₹33,824	18%	₹6,088	**₹39,912**
6	**Elevated Superstructure Surcharge (2.5m Ground Clearance for Rooftop Utility)** Make: Custom HDG High-Rise Gantry Framework • 15-Yr Structural Stability Certificate	7308	1 Job	₹35,000	₹35,000	18%	₹6,300	**₹41,300**
7	**Maintenance-Free Chemical Earthing Pits with Copper-Bonded Electrodes (3 Pits: AC, DC, LA)** Make: Ashlok 17.2mm Copper-Bonded 3-Meter Rods • 10-Yr Earth Resistance < 1 Ohm Guarantee	8544	3 Pits	₹6,500	₹19,500	18%	₹3,510	**₹23,010**
8	**Early Streamer Emission (ESE) Lightning Arrester with 60-Meter Protection Radius** Make: Eritech / ABB ESE Terminal with Digital Strike Counter • 5-Yr Comprehensive Warranty	8535	1 Set	₹22,000	₹22,000	18%	₹3,960	**₹25,960**
9	**Remote IoT Monitoring Gateway with Bi-Directional Cloud Telemetry & RS485 Modbus** Make: SolarEdge / Sungrow Cellular Smart Dongle (4G LTE) • 5-Yr Cloud Server Subscription Included	8517	1 Unit	₹12,500	₹12,500	18%	₹2,250	**₹14,750**
10	**Armoured 4-Core XLPE Aluminium AC Cable for Inverter to Main LT Panel Connection** Make: Polycab 1100V Grade 16 sq.mm 4-Core Armoured Cable (45 Meters) • 5-Yr Cable Integrity Warranty	8544	45 Mtrs	₹380	₹17,100	18%	₹3,078	**₹20,178**
11	**DG Synchronization Unit & Zero Export Controller (Prevents Reverse Power Flow to Diesel Generator)** Make: Elmeasure Smart Zero-Export Energy Manager • 3-Yr Manufacturer Warranty	9031	1 Unit	₹42,000	₹42,000	18%	₹7,560	**₹49,560**
12	**Annual Maintenance Contract (Comprehensive Preventive Bi-Monthly Cleaning, Thermography & Health Checks)** Make: AB Energy Solutions Dedicated O&M Service Team • 1st Year Free AMC Service SLA	9987	1 Yr	₹18,000	₹18,000	18%	₹3,240	**₹21,240**

(Financial Summary and Terms continue on next page !')

Amount in Words: Rupees Two Lakh Eighty-Eight Thousand Seven Hundred Fifty-Five Only

ESTIMATED GENERATION & SOLAR PAYBACK

Estimated Annual Yield: ~7,500 kWh / yr

Annual Grid Bill Savings: ~ ¹61,500 / yr

25-Year Cumulative Savings: ~ ¹15,37,500

Estimated Simple Payback: ~3.4 Years

*Calculated at 1,450 kWh/kWp specific yield & ¹8.20/kWh average grid tariff.

*Actual solar generation depends on local irradiance and rooftop tilt angle.

Gross Equipment Subtotal:	¹2,71,200
Commercial Discount:	- ¹9,117
Net Taxable Base Value:	**¹2,62,083**
Integrated GST (IGST):	¹0
FINAL CONTRACT VALUE:	**¹2,88,755**
PM Surya Ghar Subsidy (Direct Benefit):	- ¹78,000
Indicative Net Out-of-Pocket:	**¹2,10,755**

MILESTONE PAYMENT SCHEDULE & TERMS

- 40% Advance on signing contract and engineering layout signoff.
- 40% Upon warehouse material dispatch & physical site delivery.
- 20% Upon successful system testing, commissioning & net-metering synchronization.
- Quotation validity is 14 days from date of issue.

For AB Energy Solutions (Authorized Signatory):

Vikram Mehta

Client Acceptance Signature:

I accept the above proposal terms & BOM scope.