AB ENERGY SOLUTIONS

Certified Tier-1 Solar EPC & Clean Energy Infrastructure • GSTIN: 29AABCS1429B1Z8
Indiranagar, Bengaluru, KA 560038 • support@abenergy.in • +91 80 4920 1888

TECHNO-COMMERCIAL PROPOSAL

REF: QT-2026-00026-V1 (Ver 1)
Date: 23/10/2026

CLIENT & PROJECT DETAILS

Client Name: Vijayraj
Contact Phone: +91 96261 98222
Site Location: Yercaud ,salem, Bengaluru

TECHNICAL SIZING SPECIFICATIONS

System Capacity: 7 kW DC (7.47 kWp)
Package Tier: Premium Bifacial
Valid Until: 2026-11-06 (14 Days) • Sales: Karthik Raja

EQUIPMENT BILL OF MATERIALS (BOM) & STATUTORY GST BREAKDOWN

#	MATERIAL / SCOPE OF WORK	HSN/SAC	QTY	RATE (₹)	TAXABLE (₹)	GST %	TAX (₹)	TOTAL (₹
1	**13 × Jinko 575W Tiger Neo N-Type TOPCon Bifacial Module** Make: Jinko 575W Tiger Neo N-Type TOPCon Bifacial Module • 12-Yr Product / 25-Yr Linear Performance	8541	13 Nos	₹12,800	₹1,66,400	**5%**	₹8,320	**₹1,74,720**
2	**10 kW Three-Phase 415V Grid Inverter with Dual MPPT & DC Switch** Make: Sungrow SG10RT 3-Phase • 10-Yr Replacement Warranty	8504	1 Unit	₹68,000	₹68,000	**5%**	₹3,400	**₹71,400**
3	**Heavy Duty 80-micron HDG elevated mounting structure with SS304 fasteners** Make: AB Solar HDG Custom Fabricated • 10-Yr Anti-Corrosion Warranty	7308	7 kW	₹2,800	₹19,600	**18%**	₹3,528	**₹23,128**
4	**ACDB & DCDB with Type-II SPDs, Polycab Solar DC/AC Cables, Chemical Earthing Pits & ESE Lightning Arrester** Make: Schneider / L&T / Polycab • 5-Yr Comprehensive Warranty	8544	1 Set	₹33,600	₹33,600	**18%**	₹6,048	**₹39,648**
5	**Complete civil mounting, cable routing in conduits, safety labeling, DISCOM net-metering liaison and synchronization** Make: AB Energy Solutions Certified EPC Crew • 5-Yr Comprehensive Workmanship & O&M	9954	1 Turnkey	₹29,400	₹29,400	**18%**	₹5,292	**₹34,692**

Amount in Words: Rupees Three Lakh Forty Three Thousand Five Hundred Eighty Eight Only

ESTIMATED GENERATION & SOLAR PAYBACK

Estimated Annual Yield: ~10,832 kWh / yr

Annual Grid Bill Savings: ~ ₹88,822 / yr

25-Year Cumulative Savings: ~ ₹22,20,550

Estimated Simple Payback: ~3 Years

*Calculated at 1,450 kWh/kWp specific yield & ₹8.20/kWh average grid tariff.
*Actual solar generation depends on local irradiance and rooftop tilt angle.

Gross Equipment Subtotal:	₹3,17,000
Net Taxable Base Value:	**₹3,17,000**
Central GST (CGST):	₹13,294
State GST (SGST):	₹13,294
FINAL CONTRACT VALUE:	**₹3,43,588**
PM Surya Ghar Subsidy (Direct Benefit):	- ₹78,000
Indicative Net Out-of-Pocket:	**₹2,65,588**

MILESTONE PAYMENT SCHEDULE & TERMS

- 40% Advance on project booking and detailed engineering approval.
- 50% upon material dispatch against warehouse delivery challan.
- 10% upon successful DISCOM net-metering synchronization and commissioning sign-off.
- Quotation valid for 14 calendar days from date of issuance.

For AB Energy Solutions (Authorized Signatory):

Karthik Raja

Client Acceptance Signature:

I accept the above proposal terms & BOM scope.