AB ENERGY SOLUTIONS
SOLAR | ELECTRICAL | O&M

GST: 33FSQPA3244H1ZU
Solar EPC • Electrical Infrastructure • O&M
TNEB C-Licence Certified Enterprise

Quotation for 5 kW Grid-Connected Rooftop Solar Power System

Turnkey Engineering, Procurement, Installation & Commissioning Proposal

Quotation No.: QT-TEST-SHORT-001 Package Tier: Premium Tier-1 **Date: 26/10/2026**



CUSTOMER DETAILS

Client Name: **Muthusamy**

Phone: **+91 98421 23456**

Service Number: **045310081264 / 5KWp**

Site Address:
West Rajapalayam, P.N palayam, TN

Quoted Capacity: **5 kW On-Grid Solar**

Proposal Type: **Grid-Tied Rooftop EPC**

Plant Capacity	Estimated Annual Yield	Module Performance
5 kW On-Grid	**~7,500 Units**	**25-30 Years Tier-1**

Subject: Proposal for Supply, Installation, Testing & Commissioning of 5 kW Grid-Connected Rooftop Solar Power System

Dear Sir,

Thank you for giving us the opportunity to submit our quotation for your 5 kW Solar Rooftop Project. We are pleased to offer our professional turnkey services as detailed below.

The quotation includes the complete supply, installation, testing, and commissioning of a Grid-Connected Solar Rooftop System.

ABOUT AB ENERGY SOLUTION

AB Energy Solution is a trusted Solar EPC & Electrical Engineering Company specializing in Project Management Consultancy (PMC), Owner's Engineer Services, Solar EPC, Installation, Testing & Commissioning (I&C), HT/LT Electrical Works, and Solar Material Supply.

With 12+ years of industry experience, we have successfully completed 50+ Solar & Electrical Projects across Residential, Commercial, Industrial, and Agricultural sectors. Our team includes TNEB C Licence Certified Engineers and experienced professionals dedicated to delivering projects with the highest standards of Quality, Safety, and On-Time Delivery.

We provide complete end-to-end solar solutions, from Site Survey, Design, Engineering, Procurement, Installation, Testing & Commissioning to Net Metering, CEIG Documentation, and Annual Maintenance (O&M).

Quality & Compliance Assurance

All engineering designs, structural fabrications, module installations, and electrical grid synchronizations are performed strictly complying with MNRE standards, CEA technical regulations, DISCOM grid codes, and TANGEDCO net-metering protocols.

AB ENERGY
SOLUTIONS
SOLAR | ELECTRICAL | O&M

OUR SERVICES

- Solar Rooftop EPC Projects
- Ground Mounted Solar Power Plants
- Project Management Consultancy (PMC)
- Owner's Engineer Services
- Installation, Testing & Commissioning (I&C)
- Solar Water Pump Systems
- HT & LT Electrical Works
- Transmission Line & Pole Yard Works
- Net Metering & CEIG Approval Support
- Operation & Maintenance (O&M)
- Solar Material Supply

WHY CHOOSE AB ENERGY SOLUTION?

- 12+ Years of Industry Experience
- 50+ Successfully Completed Projects
- TNEB C Licence Certified Engineers
- Quality Workmanship & Safety Standards
- Professional Project Management
- On-Time Project Delivery
- Transparent Communication
- Reliable After-Sales Support

Our Commitment

Quality • Safety • Innovation • Integrity • Customer Satisfaction

Our Vision

"To deliver sustainable, reliable, and high-quality solar energy solutions that create long-term value for our customers and contribute to a greener future."

Scope of Work

We will execute the complete following turnkey EPC activities:

- Site Survey
- Engineering Support
- Supply of Material
- Complete Installation
- Testing & Commissioning
- Service Support

Bill Of Materials

S.NO	MATERIALS	SPECIFICATION	MAKE	UNITS	QUANTITY
1	**Solar Panels**	600-630Wp N-Topcon Bifacial	Waaree / Vikram	KWp	**5**
2	**Inverter**	5KW 3-Phase MPPT	Solis / Sungrow	Nos	**1**
3	**Structure**	Hot-dip Galvanized 80 Micron	Reputed	Set	**1**
4	**DCDB / ACDB**	32A MCB with Type-II SPD	Reputed	Nos	**2**
5	**Cables & Earth**	4/6 Sqmm Cu + Copper Bonded Electrodes	Polycab	Lot	**1**

Note: As this project is proposed under the Government Subsidy Scheme, all supplied solar modules must comply with the Domestic Content Requirement (DCR) guidelines.

AB ENERGY
SOLUTIONS
SOLAR | ELECTRICAL | O&M

Client Scope

- '¢ Provide a shadow-free installation area.
- '¢ Minor civil works, if required.
- '¢ Statutory charges for Bi-Directional Net Meter.
- '¢ Non-statutory charges related to Net Metering.
- '¢ Additional charges for elevated structures (if applicable).
- '¢ SIM card for the Wi-Fi monitoring dongle / APFC.

Features and Warranty

- Tier-1 High-Efficiency Solar Modules
- Inverter Warranty: Up to 8 Years
- Solar Module Product Warranty: 12 Years
- Solar Module Performance Warranty: Up to 30 Years
- Workmanship Warranty: 1 Year
- Estimated Energy Generation: ~25 kWh/day
- Non DCR / DCR Solar Panels as applicable
- Compliant with MNRE and DISCOM Standards

System Capacity & Pricing

System Capacity	Domestic Price (Including GST)	Govt Subsidy / Net Cost
5KW On-grid Solar System	**¹3,00,000/-**	**Subsidy: ¹78,000** **Net Cost: ¹2,22,000/-**

Payment Terms

- **90% Advance Payment with Purchase Order / Agreement**
- **10% After Successful Commissioning & Grid Synchronization**

Terms & Conditions

- Quotation Validity: 7 Days from issue date.
- GST is included in the above quoted price.
- Additional civil work will be charged extra 800/kW.
- Net Meter approval is subject to TANGEDCO / DISCOM regulations.
- Delivery is subject to material readiness and site access.
- Any additional civil or electrical work outside the quoted scope will be charged extra.
- Elevated above 4 Feet mounting structures will be charged extra 2500 per kW.
- Force majeure conditions and DISCOM grid outages are excluded.

Thank you for your valuable opportunity. We look forward to delivering a reliable solar solution and building a long-term partnership with you.

Contact Details

A Boopathi BE.,
CEO & Managing Director • AB ENERGY SOLUTIONS
Phone: +91 95664 99678 | Email: abenergysolutiontn@gmail.com
1/359, Maruthi Nagar, Chinnakavandanur, Namakkal, TN - 636202
12+ Years Solar Experience • TNEB C-Licence Certified Enterprise

For AB ENERGY SOLUTIONS

Authorized Signatory

AB ENERGY
SOLUTIONS
SOLAR | ELECTRICAL | O&M