AB ENERGY SOLUTIONS
SOLAR | ELECTRICAL | O&M

GST: 33FSQPA3244H1ZU

TNEB C-Licence Certified Enterprise

Quotation for 23.1 kW Grid-Connected Rooftop Solar Power System

Quotation No.: QT-2026-00028-V1 **Date: 04/11/2026**



CUSTOMER DETAILS

Client Name: **bharani**

System Type: **Rooftop Solar PV System**

Quoted Capacity: **23.1 kW On-Grid Solar**

Proposal Type: **Final_Technical**

Phone: **8920289292**

Site Address:
gandhi road ,coimbatore, salem

Subject: Proposal for Supply, Installation, Testing & Commissioning of 23.1 kW Grid-Connected Rooftop Solar Power System

Dear Sir,

Thank you for giving us the opportunity to submit our quotation for your 23.1 kW Solar Rooftop Project. We are pleased to offer our professional turnkey services as detailed below.

The quotation includes the complete supply, installation, testing, and commissioning of a Grid-Connected Solar Rooftop System.

ABOUT AB ENERGY SOLUTION

AB Energy Solution is a trusted Solar EPC & Electrical Engineering Company specializing in Project Management Consultancy (PMC), Owner's Engineer Services, Solar EPC, Installation, Testing & Commissioning (I&C), HT/LT Electrical Works, and Solar Material Supply.

With 12+ years of industry experience, we have successfully completed 50+ Solar & Electrical Projects across Residential, Commercial, Industrial, and Agricultural sectors. Our team includes TNEB C Licence Certified Engineers and experienced professionals dedicated to delivering projects with the highest standards of Quality, Safety, and On-Time Delivery.

We provide complete end-to-end solar solutions, from Site Survey, Design, Engineering, Procurement, Installation, Testing & Commissioning to Net Metering, CEIG Documentation, and Annual Maintenance (O&M).

Quality & Compliance Assurance

All engineering designs, structural fabrications, module installations, and electrical grid synchronizations are performed strictly complying with MNRE standards, CEA technical regulations, DISCOM grid codes, and TANGEDCO net-metering protocols.

AB ENERGY
SOLUTIONS
SOLAR | ELECTRICAL | O&M

OUR SERVICES

- Solar Rooftop EPC Projects
- Ground Mounted Solar Power Plants
- Project Management Consultancy (PMC)
- Owner's Engineer Services
- Installation, Testing & Commissioning (I&C)
- Solar Water Pump Systems
- HT & LT Electrical Works
- Transmission Line & Pole Yard Works
- Net Metering & CEIG Approval Support
- Operation & Maintenance (O&M)
- Solar Material Supply

WHY CHOOSE AB ENERGY SOLUTION?

- 12+ Years of Industry Experience
- 50+ Successfully Completed Projects
- TNEB C Licence Certified Engineers
- Quality Workmanship & Safety Standards
- Professional Project Management
- On-Time Project Delivery
- Transparent Communication
- Reliable After-Sales Support

Our Commitment

Quality • Safety • Innovation • Integrity • Customer Satisfaction

Our Vision

"To deliver sustainable, reliable, and high-quality solar energy solutions that create long-term value for our customers and contribute to a greener future."

AB ENERGY
SOLUTIONS
SOLAR | ELECTRICAL | O&M

Scope of Work

We will execute the complete following turnkey EPC activities:

- Site Survey
- Engineering Support
- Supply of Material
- Subsidy Support
- Complete Installation
- Testing & Commissioning
- Service Support

Bill Of Materials

S.NO	MATERIALS	SPECIFICATION	UNITS	QUANTITY
1	**solar panels**	600-630Wp N-Topcon	KWp	**23**
2	**MC4 Connector**	1000V DC, IP68	Sets	**3**
3	**DC cable**	6sqmm copper cable	Mtrs	**200**
4	**AC Cable**	3.5 Core × 35 Sq.mm al.armd Cable	Mtrs	**35**
5	**SS Bolt &Nuts**	M8x25 SS203 grade	Sets	**1**
6	**Other Accessories**	As Required	Sets	**1**
7	**Inverter**	23.1KW/3 Phase	Nos	**1**
8	**Structure**	GP Structure	Set	**1**
9	**DCDB**	63A With SPD	Nos	**1**
10	**ACDB**	3PN/63A MCB	Nos	**1**
11	**Earth Electrode**	Coper Bonded 100 Micron, 19mm dia, 1Mtr	Nos	**3**
12	**Earthing Wire**	6 Sq mm Copper wire	Mtrs	**90**
13	**Lightning Arrester**	Coper Bonded 100 Micron, 19mm dia, 1Mtr	Nos	**1**
14	**PVC pipe**	1 inch	Nos	**1**

Note: As this project is proposed under the Government Subsidy Scheme, all supplied solar modules must comply with the Domestic Content Requirement (DCR) guidelines.

Client Scope

- Provide a shadow-free installation area.
- Rooftop access and electricity/water for testing.
- Statutory charges for Bi-Directional Net Meter.
- Non-statutory charges related to Net Metering.
- Additional charges for elevated structures (if applicable).
- SIM card for the Wi-Fi monitoring dongle / APFC.

Features and Warranty

- High-Efficiency Solar Modules
- Inverter Warranty: Up to 8 Years
- Solar Module Product Warranty: 12 Years
- Solar Module Performance Warranty: Up to 30 Years
- Workmanship Warranty: 1 Year
- Estimated Energy Generation: ~116 kWh/day
- Non DCR / DCR Solar Panels as applicable
- Compliant with MNRE and DISCOM Standards

System Capacity & Subsidy Details

System Capacity	Domestic Price (Incl. GST)	Govt. Subsidy Support	Net Customer Cost
23.1 kW On-Grid Solar	**Rs. 8,91,922/-**	**Rs. 78,000** (Direct DBT Support)	**Rs. 8,13,922/-** (Net Payable Investment)

Payment Terms

- **90% Advance Payment with Purchase Order / Agreement**
- **10% After Successful Commissioning & Grid Synchronization**

AB ENERGY
SOLUTIONS
SOLAR | ELECTRICAL | O&M

Terms & Conditions

- Quotation Validity: 7 Days from issue date.
- GST is included in the above quoted price.
- Custom structural elevations beyond standard height will be charged extra.
- Net Meter approval is subject to TANGEDCO / DISCOM regulations.
- Delivery is subject to material readiness and site access.
- Any additional cabling or elevated structure work outside the quoted scope will be charged extra.
- Pre-engineered HDG solar mounting structures included in scope.
- Force majeure conditions and DISCOM grid outages are excluded.

Contact Details

A Boopathi BE.,
CEO & Managing Director • AB ENERGY SOLUTIONS
Phone: +91 95664 99678 | Email: abenergysolutiontn@gmail.com
1/359, Maruthi Nagar, Chinnakavandanur, Namakkal, TN - 636202
12+ Years Solar Experience • TNEB C-Licence Certified Enterprise

For AB ENERGY SOLUTIONS

Authorized Signatory

Thank you for your valuable opportunity. We look forward to delivering a reliable solar solution and building a long-term partnership with you.